

Australian Standard[®]

Pipelines—Gas and liquid petroleum

Part 1: Design and construction



This Australian Standard® was prepared by Committee ME-038, Petroleum Pipelines. It was approved on behalf of the Council of Standards Australia on 19 January 2007. This Standard was published on 25 May 2007.

The following are represented on Committee ME-038:

- APIA Research and Standards Committee
 - Australasian Corrosion Association
 - Australian Chamber of Commerce and Industry
 - Australian Institute of Petroleum
 - Australian Pipeline Industry Association
 - Bureau of Steel Manufacturers of Australia
 - Department of Consumer and Employment Protection (WA)
 - Department of Energy, Utilities and Sustainability (NSW)
 - Department of Mines and Energy (Qld)
 - Department of Primary Industries (Victoria)
 - Department of Primary Industry, Fisheries and Mines (NT)
 - Energy Networks Association
 - Gas Association of New Zealand
 - Primary Industries and Resources SA
 - Welding Technology Institute of Australia
-

This Standard was issued in draft form for comment as DR 04561.

Standards Australia wishes to acknowledge the participation of the expert individuals that contributed to the development of this Standard through their representation on the Committee and through the public comment period.

Keeping Standards up-to-date

Australian Standards® are living documents that reflect progress in science, technology and systems. To maintain their currency, all Standards are periodically reviewed, and new editions are published. Between editions, amendments may be issued.

Standards may also be withdrawn. It is important that readers assure themselves they are using a current Standard, which should include any amendments that may have been published since the Standard was published.

Detailed information about Australian Standards, drafts, amendments and new projects can be found by visiting www.standards.org.au

Standards Australia welcomes suggestions for improvements, and encourages readers to notify us immediately of any apparent inaccuracies or ambiguities. Contact us via email at mail@standards.org.au, or write to Standards Australia, GPO Box 476, Sydney, NSW 2001.

Australian Standard[®]

Pipelines—Gas and liquid petroleum

Part 1: Design and construction

First published in part as part of AS CB28—1972.
Revised and redesignated AS 1697—1975.
AS 1958 first published 1976.
AS 2018 first published 1977.
Second edition AS 1697—1979.
Third edition 1981.
Second edition AS 1958—1981.
Second edition AS 2018—1981.
AS 1958—1981 and parts of AS 1697—1981 and AS 2018—1981
revised, amalgamated and redesignated AS 2885—1987.
Parts of AS 1697—1981, AS 2018—1981 and AS 2885—1987
revised, amalgamated and redesignated in part as AS 2885.1—1997.
Second edition 2007.
Reissued incorporating Amendment No. 1 (February 2009).

COPYRIGHT

© Standards Australia

All rights are reserved. No part of this work may be reproduced or copied in any form or by any means, electronic or mechanical, including photocopying, without the written permission of the publisher.

Published by Standards Australia GPO Box 476, Sydney, NSW 2001, Australia
ISBN 0 7337 8241 8

PREFACE

This Standard was prepared by the Joint Standards Australia/Standards New Zealand Committee ME-038, Petroleum Pipelines, to supersede AS 2885—1997, *Pipeline—Gas and liquid petroleum*.

This Standard incorporates Amendment No. 1 (February 2009). The changes required by the Amendment are indicated in the text by a marginal bar and amendment number against the clause, note, table, figure or part thereof affected.

After consultation with stakeholders in both countries, Standards Australia and Standards New Zealand decided to develop this Standard as an Australian Standard rather than an Australian/New Zealand Standard.

The objective of this Standard is to provide requirements for the design and construction of steel pipelines and associated piping and components that are used to transmit single phase and multi-phase hydrocarbon fluids.

This standard provides guidelines for use of pipe manufactured from certain non steel or corrosion-resistant materials.

This Standard is part of a series, that covers high pressure petroleum pipelines, as follows:

AS

	2885	Pipelines—Gas and liquid petroleum
A1	2885.0	Part 0: General requirements
	2885.1	Part 1: Design and construction (this Standard)
	2885.2	Part 2: Welding
	2885.3	Part 3: Operation and maintenance
	2885.4	Part 4: Submarine pipelines
A1	2885.5	Part 5: Field pressure testing
		Text deleted

A1 | **‘Text deleted’**

2007 REVISION

A1 | **‘Text deleted’**

The comprehensive revision of AS 2885.1 is the result of extensive work by subcommittee ME-038-1 in response to a request from the industry that it consider increasing the design factor from 0.72 to 0.80. This request prompted a detailed review of each section and each clause of the Standard, resulting in the preparation of some 70 ‘issue papers’ that considered the underlying technical issues (in relation to an increased design factor) and recommended changes to the Standard. These issue papers were debated within the

subcommittee and published on the Industry web site to allow consideration by the Industry. The results of these deliberations form the basis of this revision. The revision also reflects the results of a significant and ongoing industry-funded research program undertaken by the Australian Pipeline Industry Association and its research contractors, and through its association with the Pipeline Research Council International and the European Pipeline Research Group.

This revision provides a basis for Industry to benefit through the application of an increased factor for pressure design (for new pipelines) and a structured basis for increasing the MAOP of a qualifying existing pipeline. These benefits are supported by robust requirements for safety, structural design, construction, testing and record keeping.

Significant changes in this Revision include the following:

- (a) A restructure of the sections of the document to separate pipeline general, pipeline, stations, and instrumentation and control.
- (b) The incorporation of a section defining the minimum requirements for a pipeline whose maximum allowable operating pressure is proposed to be raised.
- (c) Section 2 (Safety) has been rewritten, to reflect experience gained in the seven years since it was revised to provide a mandatory requirement for risk assessment. This revision provides more explicit guidance on the obligation to undertake safety assessments with the integrity required for compliance with this Standard. Material is provided in normative and informative appendices.
- (d) Section 3 (Materials and components) has been revised to better address the treatment of materials used in pipelines. It includes a requirement to de-rate the specified minimum yield stress of pipe designed for operation at temperatures of 65°C and higher. The use of fibreglass and corrosion-resistant alloy pipe materials for pipelines constructed to this Standard is permitted and limited in this Section. A minimum toughness requirement for pipe DN 100 and larger has been introduced.
- (e) Section 4 (Pipeline general) contains most of the material in the 'Pipeline general' section of the 1997 revision. The Section has been expanded to include the following:
 - (i) A mandatory requirement for the design of a pipeline for the existing and intended land use.
 - (ii) A revision of the requirements for effective pipeline marking including a change to require the marker sign to comply with a 'danger sign' in accordance with AS 1319, *Safety signs for the occupational environment*.
 - (iii) A plan for isolation of a pipeline.
 - (iv) Special requirements for pipelines constructed in locations where the consequence of failure by rupture is not acceptable. Provisions for compliance with these requirements for pipelines constructed to this, or to an earlier revision of the Standard, in land where the location classification has changed to residential (or equal) is included.
 - (v) The location classification definitions are revised and additional sub-classes are defined.
 - (vi) The hydrostatic strength test pressure is redefined to address the situation where the pipe wall thickness exceeds the pressure design thickness, including corrosion allowance.
 - (vii) Provisions for low-temperature excursions.
 - (viii) Calculation methods for critical defect length, energy release rate and radiation contour.

- (f) The requirements for fracture control have been extensively revised to clarify the requirements and to reflect experience gained since 1997. Emphasis is placed on the use of the Battelle Two Curve model given the fact that most gas pipelines in Australia transport ‘rich’ gas.
- (g) Section 5 (Pipeline design) has been revised to incorporate those provisions specific to pipeline in the 1997 revision. Significant changes to this Section include the following:
 - (i) The pipe wall thickness is required to be the greater of the pressure design thickness, and the thickness required for each other identified load condition. The thickness terms used in this Standard are clarified.
 - (ii) An equation for calculating the thickness required for external pressure is provided.
 - (iii) Recognizing the result of a comprehensive investigation, of its purpose and the impact of change, the design factor has been changed from 0.72 to 0.80, and the design factor for pipeline assemblies and pipelines on bridges has been changed from 0.60 to 0.67.
 - (iv) **‘Text deleted’**
 - (v) Requirements for stress and strain have been completely redrafted to clarify the requirements. The limits for each stress condition are tabulated and normative and informative appendices are provided incorporating the relevant equations. Reliability and limit state design methods are permitted for pipeline design and integrity analysis, using approved methods.
 - (vi) The requirements for a ‘prequalified’ design are included in a new clause. This is permitted for short pipelines DN 200 and smaller with a MAOP of 10.2 MPa or less.
 - (vii) The provisions for reduced cover for a pipeline constructed through ‘rock’ have been revised.
 - (viii) The method for calculating reinforcement of branch connections in AS 2885.1—1987 has been reinstated in full.
- (h) Section 6 (Station design) incorporates the provisions of Clause 4.4 of the 1997 revision in relation to stations. The Section has been expanded to require the Design Basis for stations to be documented. Additional guidance is provided on treatment of lightning, together with some clarifying revisions to the text.
- (i) Section 7 (Instrumentation and control design) incorporates the requirements of Clause 4.2 of the 1997 revision. The requirements for pipeline operation under transient conditions and a tolerance specification for pressure controls on pipelines intended to be operated at MAOP are addressed.
- (j) Section 8 (Corrosion mitigation) incorporates the requirements of Section 5 of the 1997 revision. The Section incorporates clarifying revisions.
- (k) Section 9 (Upgrade of MAOP) is a new Section that sets down the minimum process, including activities required, to demonstrate the fitness of a pipeline designed and operated at one pressure as suitable for approval for operation at a higher pressure. The Section establishes a structured methodology for demonstrating the pipeline fitness and, once approved, for commissioning the pipeline at the new pressure. The maximum pressure is limited to the hydrostatic strength test pressure divided by the equivalent test pressure factor.

A1

A1

- (l) Section 10 (Construction) incorporates Section 6 of the 1997 Standard. The requirements for construction survey are clarified, and a minimum accuracy for as-constructed survey is incorporated. Since padding and backfilling are two activities that impact on the pipeline integrity, this revision incorporates additional requirements for these activities reflecting outcomes from APIA research on backfilling.
- (m) Section 11 (Inspection and testing) has been revised to align it with the requirements of AS 2885.5. It specifies strength test endpoint requirements for pipelines with a pressure design factor of 0.80, and references APIA research and associated software designed to enable the analysis of the pipe in a proposed (and constructed) test section to be analysed to determine the presence and location of pipe that may be exposed to excessive strain at the intended strength test pressure.
- (n) Section 12 (Documentation). Obligations on the developer of a new pipeline to document the design and construction, and to transfer this information to the pipeline operator, are clarified and expanded.
- (o) Each appendix in the 1997 revision of the Standard has been critically reviewed and revised, as appropriate. New appendices are provided reflecting the findings of APIA research, clarification of concepts in the Standard, and providing detailed calculation methods.
- (p) Resistance to penetration calculation methods and design requirements provided.

In addition to the items identified above, there are a great many changes of lesser significance incorporated in the document to the extent that users should consider it as a familiar but new Standard.

2008 Amendment No. 1

Amendment No. 1 to AS 2885.1—2007 was prepared to correct errors in the 2007 revision and to clarify items identified as being potentially confusing. The amendment includes guidance on specifying fracture toughness when purchasing line pipe and includes a simplified calculation for energy release from leaks.

The requirements for the control of fracture initiation in components other than line pipe have been clarified.

An informative Appendix, which provides guidance on the design, construction and testing of fibreglass pipelines, is included.

The terms ‘normative’ and ‘informative’ have been used in this Standard to define the application of the appendix to which they apply. A ‘normative’ appendix is an integral part of a Standard, whereas an ‘informative’ appendix is only for information and guidance.

Statements expressed in mandatory terms in notes to tables and figures are deemed to be requirements of the Standard.

CONTENTS

	<i>Page</i>
SECTION 1 SCOPE AND GENERAL	
1.1 SCOPE	15
1.2 GENERAL	15
1.3 RETROSPECTIVE APPLICATION	15
1.4 REFERENCED DOCUMENTS	16
1.5 DEFINITIONS	16
1.5.1 Accessory	16
1.5.2 Approved and approval.....	16
1.5.3 As low as reasonably practicable (ALARP).....	16
1.5.4 Buckle.....	16
1.5.5 Casing.....	16
1.5.6 Collapse	16
1.5.7 Competent person	16
1.5.8 Common threats.....	16
1.5.9 Component.....	16
1.5.10 Construction	16
1.5.11 Control piping.....	16
1.5.12 Critical defect length.....	17
1.5.13 Defect	17
1.5.14 Dent	17
1.5.15 Failure.....	17
1.5.16 Fitting	17
1.5.17 Fluid	17
1.5.18 Gas.....	17
1.5.19 Heat	17
1.5.20 High consequence area	17
1.5.21 High vapour pressure liquid (HVPL)	17
1.5.22 Hoop stress	17
1.5.23 Hot tap	17
1.5.24 Inspector	18
1.5.25 Leak test	18
1.5.26 Licensee.....	18
1.5.27 Location class	18
1.5.28 May.....	18
1.5.29 Mechanical interference-fit joint.....	18
1.5.30 Nominated Standard.....	18
1.5.31 Non-credible threat	18
1.5.32 Non-location specific threat	18
1.5.33 Petroleum.....	18
1.5.34 Pig	18
1.5.35 Pig trap (scraper trap)	18
1.5.36 Pipework, mainline	18
1.5.37 Pipework, station	18
1.5.38 Piping	19
1.5.39 Pretested	19
1.5.40 Pressure, design	19
1.5.41 Pressure, maximum allowable operating (MAOP).....	19
1.5.42 Pressure, maximum operating (MOP).....	19
1.5.43 Pressure strength.....	19
1.5.44 Propagating fracture.....	19

1.5.45	Proprietary item	19
1.5.46	Protection measures, procedural	19
1.5.47	Protection measure, physical.....	19
1.5.48	Regulatory authority	19
1.5.49	Rupture	19
1.5.50	Safety management study or process	19
1.5.51	Shall.....	19
1.5.52	Should.....	19
1.5.53	Sour service	20
1.5.54	Specified minimum yield stress (SMYS)	20
1.5.55	Strength test	20
1.5.56	Telescoped pipeline	20
1.5.57	Threat	20
1.5.58	Wall thickness, design pressure	20
1.5.59	Wall thickness, required.....	20
1.5.60	Wall thickness, nominal.....	20
1.6	SYMBOLS AND UNITS	20
1.7	ABBREVIATIONS	22

SECTION 2 SAFETY

2.1	BASIS OF SECTION	24
2.2	ADMINISTRATIVE REQUIREMENTS	24
2.2.1	Approval.....	24
2.2.2	Documentation.....	25
2.2.3	Implementation.....	25
2.2.4	Safety management study validation.....	25
2.2.5	Operational Review	25
2.3	SAFETY MANAGEMENT PROCESS	26
2.3.1	General	26
2.3.2	Threats.....	27
2.3.3	Controls	29
2.3.4	Failure analysis.....	30
2.3.5	Risk assessment	31
2.3.6	Demonstration of fault tolerance.....	31
2.4	STATIONS, PIPELINE FACILITIES AND PIPELINE CONTROL SYSTEMS	31
2.4.1	General	31
2.4.2	Safety assessments.....	31
2.5	ENVIRONMENTAL MANAGEMENT	32
2.6	ELECTRICAL.....	32
2.7	CONSTRUCTION AND COMMISSIONING.....	33
2.7.1	Construction safety	33
2.7.2	Testing safety.....	34
2.7.3	Commissioning safety.....	34

SECTION 3 MATERIALS AND COMPONENTS

3.1	BASIS OF SECTION	35
3.2	QUALIFICATION OF MATERIALS AND COMPONENTS.....	35
3.2.1	General	35
3.2.2	Materials and components complying with nominated Standards	35
3.2.3	Materials and components complying with Standards not nominated in this Standard.....	36
3.2.4	Components, other than pipe, for which no Standard exists.....	37
3.2.5	Reclaimed pipe	37
3.2.6	Reclaimed accessories, valves and fittings.....	37
3.2.7	Identification of components.....	38
3.2.8	Material and components not fully identified.....	38

- 3.2.9 Unidentified materials and components 38
- 3.2.10 Hydrostatic test 38
- 3.3 REQUIREMENTS FOR COMPONENTS TO BE WELDED 38
 - 3.3.1 Welding of prequalified materials 38
 - 3.3.2 Materials specifications 38
- 3.4 ADDITIONAL MECHANICAL PROPERTY REQUIREMENTS 38
 - 3.4.1 Yield strength 38
 - 3.4.2 Pipe Yield to Tensile Ratio 38
 - 3.4.3 Strength de-rating 39
 - 3.4.4 Fracture toughness 39
- 3.5 REQUIREMENTS FOR TEMPERATURE-AFFECTED ITEMS 39
 - 3.5.1 General 39
 - 3.5.2 Items heated subsequent to manufacture 40
 - 3.5.3 Pipe operated at elevated temperatures 40
 - 3.5.4 Pipe exposed to cryogenic temperatures 40
- 3.6 MATERIALS TRACEABILITY AND RECORDS 40
- 3.7 RECORDS 40

SECTION 4 DESIGN—GENERAL

- 4.1 BASIS OF SECTION 41
- 4.2 ROUTE 42
 - 4.2.1 General 42
 - 4.2.2 Investigation 42
 - 4.2.3 Route selection 43
 - 4.2.4 Route identification 43
- 4.3 CLASSIFICATION OF LOCATIONS 44
 - 4.3.1 General 44
 - 4.3.2 Measurement length 44
 - 4.3.3 Location classification 44
 - 4.3.4 Primary location class 44
 - 4.3.5 Secondary location class 45
- 4.4 PIPELINE MARKING 46
 - 4.4.1 General 46
 - 4.4.2 Sign location 47
 - 4.4.3 Sign design 48
- 4.5 SYSTEM DESIGN 49
 - 4.5.1 Design Basis 49
 - 4.5.2 Maximum velocity 50
 - 4.5.3 Design life 50
 - 4.5.4 Maximum allowable operating pressure (MAOP) 51
 - 4.5.5 Minimum strength test pressure 52
- 4.6 ISOLATION 52
 - 4.6.1 General 52
 - 4.6.2 Isolation plan 53
 - 4.6.3 Review of isolation plan 53
 - 4.6.4 Isolation valves 53
- 4.7 SPECIAL PROVISIONS FOR HIGH CONSEQUENCE AREAS 54
 - 4.7.1 General 54
 - 4.7.2 No rupture 55
 - 4.7.3 Maximum discharge rate 55
 - 4.7.4 Change of location class 55
- 4.8 FRACTURE CONTROL 56
 - 4.8.1 General 56
 - 4.8.2 Fracture control plan 57
 - 4.8.3 Specification of toughness properties for brittle fracture control 60
 - 4.8.4 Specification of toughness properties for tearing fracture control 60

4.8.5	Critical defect length.....	63
4.9	LOW TEMPERATURE EXCURSIONS	64
4.10	ENERGY DISCHARGE RATE.....	64
4.11	RESISTANCE TO PENETRATION	65
4.11.1	General	65
4.11.2	Penetration resistance requirements	65
4.11.3	Calculation of resistance to penetration	66

SECTION 5 PIPELINE DESIGN

5.1	BASIS OF SECTION	67
5.2	DESIGN PRESSURE	67
5.2.1	Internal pressure	67
5.2.2	External pressure	67
5.3	DESIGN TEMPERATURES	68
5.4	WALL THICKNESS	68
5.4.1	Nominal wall thickness.....	68
5.4.2	Required wall thickness	69
5.4.3	Wall thickness for design internal pressure	69
5.4.4	Wall thickness for design internal pressure of bends.....	70
5.4.5	Wall thickness design for external pressure	70
5.4.6	Allowances	71
5.4.7	Pipe manufacturing tolerance.....	71
5.4.8	Wall thickness summary	71
5.5	EXTERNAL INTERFERENCE PROTECTION	73
5.5.1	General	73
5.5.2	Depth of cover	73
5.5.3	Depth of cover—Rock trench	74
5.5.4	Design for protection—General requirements.....	75
5.5.5	Physical controls.....	76
5.5.6	Procedural controls	77
5.5.7	Other protection	79
5.6	PREQUALIFIED PIPELINE DESIGN	79
5.6.1	Minimum requirements.....	79
5.6.2	Prequalified design coverage	79
5.6.3	Prequalified design does not apply.....	80
5.6.4	Prequalified design not permitted	80
5.6.5	Prequalified design special cases	80
5.7	STRESS AND STRAIN	81
5.7.1	General	81
5.7.2	Terminology	81
5.7.3	Stresses due to normal loads	82
5.7.4	Stresses due to occasional loads.....	84
5.7.5	Stresses due to construction	84
5.7.6	Hydrostatic pressure testing	84
5.7.7	Fatigue.....	85
5.7.8	Summary of stress limits.....	85
5.7.9	Plastic strain and limit state design methodologies	85
5.8	SPECIAL CONSTRUCTION	86
5.8.1	General	86
5.8.2	Above-ground piping.....	87
5.8.3	Pipeline with reduced cover or above ground	87
5.8.4	Tunnels and shafts	90
5.8.5	Directionally drilled crossings	90
5.8.6	Submerged crossings	90
5.8.7	Pipeline attached to a bridge	91
5.8.8	Road and railway reserves	92

5.9	PIPELINES ASSEMBLIES.....	95
5.9.1	General	95
5.9.2	Scraper assemblies.....	95
5.9.3	Mainline valve assembly.....	95
5.9.4	Isolating valve assembly	95
5.9.5	Branch connection assembly.....	95
5.9.6	Attachment of pads, lugs and other welded connections	96
5.9.7	Special fabricated assemblies.....	96
5.10	JOINTING.....	97
5.10.1	General	97
5.10.2	Welded joints.....	97
5.10.3	Flanged joints	97
5.10.4	Threaded fittings.....	98
5.10.5	Other types.....	98
5.11	SUPPORTS AND ANCHORS	98
5.11.1	General	98
5.11.2	Settlement, scour, and erosion	99
5.11.3	Design.....	99
5.11.4	Forces on an above-ground pipeline.....	99
5.11.5	Attachment of anchors, supports, and clamps	99
5.11.6	Restraint due to soil friction.....	99
5.11.7	Anchorage at a connection	100
5.11.8	Support of branch connections.....	100
SECTION 6 STATION DESIGN		
6.1	BASIS OF SECTION	101
6.2	DESIGN	101
6.2.1	Location.....	101
6.2.2	Layout.....	102
6.2.3	Other considerations	102
6.2.4	Safety.....	102
6.3	STATION PIPEWORK	105
6.3.1	Design standard	105
6.3.2	Pipework subject to vibration.....	105
6.4	STATION EQUIPMENT.....	105
6.4.1	General	105
6.4.2	Pressure vessels	106
6.4.3	Proprietary equipment.....	106
6.4.4	Equipment isolation	106
6.4.5	Station valves.....	106
6.5	STRUCTURES.....	107
6.5.1	General	107
6.5.2	Buildings	107
6.5.3	Below-ground structures	107
6.5.4	Corrosion protection	108
6.5.5	Electrical installations.....	108
6.5.6	Drainage	108
SECTION 7 INSTRUMENTATION AND CONTROL DESIGN		
7.1	BASIS OF SECTION	110
7.2	CONTROL AND MANAGEMENT OF PIPELINE SYSTEM.....	110
7.2.1	Pipeline pressure control.....	110
7.2.2	Separation of pipeline sections with different MAOP	112
7.2.3	Pipeline facility control.....	112
7.3	FLUID PROPERTY LIMITS	112

7.4	SCADA—SUPERVISORY CONTROL AND DATA ACQUISITIONS SYSTEM	112
7.5	COMMUNICATION	113
7.6	CONTROL FACILITIES	113

SECTION 8 MITIGATION OF CORROSION

8.1	BASIS OF SECTION	114
8.2	PERSONNEL	114
8.3	RATE OF DEGRADATION	114
8.3.1	Assessment	114
8.3.2	Internal corrosion	115
8.3.3	External corrosion	115
8.3.4	Environmentally assisted cracking	115
8.3.5	Microbiologically induced corrosion (MIC)	115
8.4	CORROSION MITIGATION METHODS	115
8.4.1	General	115
8.4.2	Corrosion mitigation methods	115
8.5	CORROSION ALLOWANCE	116
8.6	CORROSION MONITORING	116
8.7	INTERNAL CORROSION MITIGATION METHODS	117
8.7.1	General	117
8.7.2	Internal lining	117
8.7.3	Corrosion inhibitors and biocides	117
8.7.4	Corrosion-resistant materials	118
8.8	EXTERNAL CORROSION MITIGATION METHODS	118
8.8.1	General	118
8.8.2	Coating	118
8.8.3	Cathodic protection	119
8.8.4	Design considerations	119
8.8.5	Measurement of potential	120
8.8.6	Electrical earthing	121
8.9	EXTERNAL ANTI-CORROSION COATING	121
8.9.1	Coating system	121
8.9.2	Coating selection	121
8.9.3	Coating application	121
8.9.4	Joint and coating repair	122
8.10	INTERNAL LINING	122
8.10.1	Pipeline lining	122
8.10.2	Joint and lining repair	122

A1 |

SECTION 9 UPGRADE OF MAOP

9.1	BASIS OF SECTION	123
9.2	MAOP UPGRADE PROCESS	123
9.2.1	Process stages	123
9.2.2	Upgrade Design Basis	123
9.2.3	Data collection	124
9.2.4	Engineering analysis	125
9.2.5	Safety management study	127
9.2.6	Rectification	127
9.2.7	Revised MAOP	127
9.2.8	Approval	127
9.2.9	Commissioning and testing	127
9.2.10	Records	127

SECTION 10 CONSTRUCTION

10.1	BASIS OF SECTION	128
10.2	SURVEY	128
10.2.1	General	128
10.2.2	Survey accuracy	128
10.2.3	Horizontal directional drilled installation.....	128
10.2.4	Records	129
10.3	HANDLING OF PIPE AND COMPONENTS.....	129
10.3.1	General	129
10.3.2	Pipe transport.....	129
10.3.3	Construction loads	129
10.4	INSPECTION OF PIPE AND COMPONENTS	130
10.4.1	General	130
10.4.2	Ovality	130
10.4.3	Buckles	130
10.4.4	Dents.....	130
10.4.5	Gouges, grooves and notches	130
10.4.6	Repair of defects	130
10.4.7	Laminations and notches.....	131
10.5	CHANGES IN DIRECTION	131
10.5.1	Accepted methods for changes in direction.....	131
10.5.2	Internal access.....	131
10.5.3	Changing direction at a butt weld	131
10.5.4	Bend fabricated from a forged bend or elbow	131
10.5.5	Roped bends	131
10.6	COLD-FIELD BENDS	131
10.6.1	General	131
10.6.2	Qualification of cold-field bending procedure.....	132
10.6.3	Acceptance limits for field bends.....	132
10.7	FLANGED JOINTS	133
10.8	WELDED JOINTS	133
10.9	COVERING SLABS, BOX CULVERTS, CASINGS AND TUNNELS.....	133
10.10	SYSTEM CONTROLS.....	133
10.11	ATTACHMENT OF ELECTRICAL CONDUCTORS	134
10.11.1	General	134
10.11.2	Aluminothermic welding	134
10.12	LOCATION.....	135
10.12.1	Position.....	135
10.12.2	Clearances.....	135
10.13	CLEARING AND GRADING.....	135
10.14	TRENCH CONSTRUCTION	135
10.14.1	Safety.....	135
10.14.2	Separation of topsoil	136
10.14.3	Dimensions of trenches.....	136
10.14.4	Bottoms of trenches	136
10.14.5	Scour.....	136
10.15	INSTALLATION OF A PIPE IN A TRENCH	136
10.15.1	General	136
10.15.2	Installation requirement	136
10.15.3	Development of specifications and procedures	137
10.16	PLOUGHING-IN AND DIRECTIONALLY DRILLED PIPELINES	137
10.16.1	General	137
10.16.2	Testing of coating integrity within directionally drilled installations	138
10.17	SUBMERGED CROSSINGS	138
10.18	REINSTATEMENT	138

10.19 TESTING OF COATING INTEGRITY OF BURIED PIPELINES	138
10.20 CLEANING AND GAUGING PIPELINES	139

SECTION 11 INSPECTIONS AND TESTING

11.1 BASIS OF SECTION	140
11.2 INSPECTION AND TEST PLAN AND PROCEDURES.....	140
11.3 PERSONNEL	140
11.4 PRESSURE TESTING	140
11.4.1 Application	140
11.4.2 Exemptions from a field pressure test	140
11.4.3 Pre-tested pipe	140
11.4.4 Test procedure	141
11.4.5 Strength test pressures	141
11.4.6 Testing with air or gas	141
11.4.7 Pressure-testing loads	142
11.4.8 Acceptance criteria	143
11.5 COMMENCEMENT OF PATROLLING.....	143

A1 |

SECTION 12 DOCUMENTATION

12.1 RECORDS.....	144
12.2 RETENTION OF RECORDS	145

APPENDICES

A REFERENCED DOCUMENTS	146
B SAFETY MANAGEMENT PROCESS	151
C THREAT IDENTIFICATION	157
D DESIGN CONSIDERATIONS FOR EXTERNAL INTERFERENCE PROTECTION	161
E EFFECTIVENESS OF PROCEDURAL CONTROLS FOR THE PREVENTION OF EXTERNAL INTERFERENCE DAMAGE TO PIPELINES	164
F QUALITATIVE RISK ASSESSMENT.....	171
G ALARP.....	175
H INTEGRITY OF THE SAFETY MANAGEMENT PROCESS.....	177
I ENVIRONMENTAL MANAGEMENT	185
J PREFERRED METHOD FOR TENSILE TESTING OF WELDED LINE PIPE DURING MANUFACTURE.....	187
K FRACTURE TOUGHNESS TEST METHODS	188
L FRACTURE CONTROL PLAN FOR STEEL PIPELINES.....	190
M CALCULATION OF RESISTANCE TO PENETRATION.....	200
N FATIGUE.....	205
O FACTORS AFFECTING CORROSION	208
P ENVIRONMENT-RELATED CRACKING.....	211
Q INFORMATION FOR CATHODIC PROTECTION.....	218
R MITIGATION OF EFFECTS FROM HIGH VOLTAGE ELECTRICAL POWERLINES	220
S PROCEDURE QUALIFICATION FOR COLD FIELD BENDS.....	228
T GUIDELINES FOR THE TENSIONING OF BOLTS IN THE FLANGED JOINTS OF PIPING SYSEMS.....	233
U STRESS TYPES AND DEFINITIONS	249
V EXTERNAL LOADS	256
W COMBINED EQUIVALENT STRESS	260
X PIPE STRESS ANALYSIS.....	270
Y RADIATION CONTOUR	275
Z REINFORCEMENT OF WELDED BRANCH CONNECTIONS	280

A1		AA FIBREGLASS PIPE—MANUFACTURE, DESIGN AND CONSTRUCTION CONSIDERATIONS.....	286
----	--	--	-----

STANDARDS AUSTRALIA

Australian Standard Pipelines—Gas and liquid petroleum

Part 1: Design and construction

SECTION 1 SCOPE AND GENERAL

1.1 SCOPE

This Standard specifies requirements for design and construction of carbon and carbon-manganese steel pipelines and associated piping and components that are used to transmit single-phase and multi-phase hydrocarbon fluids, such as natural and manufactured gas, liquefied petroleum gas, natural gasoline, crude oil, natural gas liquids and liquid petroleum products.

The principles are expressed in practical rules and guidelines for use by competent persons.

The fundamental principles and the practical rules and guidelines set out in AS 2885.1, AS 2885.2, AS 2885.3 and AS 2885.5 are the basis on which an engineering assessment is to be made where these Standards do not provide detailed requirements appropriate to a specific item.

NOTE: AS 2885.4 for offshore submarine pipeline systems is a standalone document.

1.2 GENERAL

Where approved, this Standard may also be used for design and construction of pipelines made with corrosion-resistant alloy steels, fibreglass and other composite materials. Where this Standard is used for pipelines fabricated from these materials, appropriate requirements shall be established to replace the provisions of this Standard in relation to nominated standards for materials (Section 3), fracture control (Clause 4.8), stress and strain (Clause 5.7) and corrosion (Section 8) and the provisions of AS 2885.2 in relation to welding and non-destructive examination. For composite material, appropriate requirements shall be established to replace the hydrostatic strength test endpoint provisions of AS 2885.5.

Where this Standard imposes requirements, which add to or override the requirements of a permitted Standard or code, the additional requirements are explicitly stated in this Standard and shall be met.

1.3 RETROSPECTIVE APPLICATION

A1 | Retrospectivity is governed by AS 2885.0.

AS 2885.1—2007 introduces changes that reflect matters of public safety in high consequence areas and which are intended to apply retrospectively.

Each existing pipeline shall be assessed against the requirements of Clauses 4.7.2 and 4.7.3. Where the existing pipeline does not comply with either Clause, mitigation shall be applied in accordance with Clause 4.7.4 regardless of whether or not there has been a land use change.