

AS 4198:2022



Precast concrete access and maintenance chambers for sewerage applications



AS 4198:2022

This Australian Standard ® was prepared by WS-006, Concrete Pipes. It was approved on behalf of the Council of Standards Australia on 4 March 2022.

This Standard was published on 18 March 2022.

The following are represented on Committee WS-006:

- Australian Chamber of Commerce and Industry
- Australian Institute of Building
- Austroads
- Concrete Institute of Australia
- Concrete Pipe Association of Australasia
- Engineers Australia
- National Precast Concrete Association Australia
- University of New South Wales
- Water Services Association of Australia

Additional Interests

- Auckland Council
- Business New Zealand
- Concrete New Zealand Precast

This Standard was issued in draft form for comment as DR AS 4198:2020.

Keeping Standards up-to-date

Ensure you have the latest versions of our publications and keep up-to-date about Amendments, Rulings, Withdrawals, and new projects by visiting:

www.standards.org.au

ISBN 978 1 76113 685 6

Precast concrete access and maintenance chambers for sewerage applications

First published as AS 4198—1994.
Second edition 2022.

© Standards Australia Limited 2022

All rights are reserved. No part of this work may be reproduced or copied in any form or by any means, electronic or mechanical, including photocopying, without the written permission of the publisher, unless otherwise permitted under the Copyright Act 1968 (Cth).

Preface

This Standard was prepared by the Standards Australia Committee WS-006, Concrete Pipes, to supersede AS 4198:1994, *Precast concrete access chambers for sewerage applications*.

The objective of this Standard is to provide a performance-based document for precast concrete access and maintenance chambers.

The major changes in this edition are as follows:

- (a) Durability has been enhanced with additional requirements covering reinforcement and concrete materials, as well as production, placement and curing of concrete. This edition also introduces a new exposure classification for chambers in sewer applications.
- (b) Precast concrete maintenance chambers have been incorporated into this Standard.
- (c) An increase in the maximum depth of chambers and the maximum nominal diameter of chambers and an increase in the maximum diameter of connecting pipes. Additional testing requirements and test methods have been included that accompany these changes in diameter and depth.
- (d) Updates to the load testing requirements to accommodate larger diameter chambers and also changes in road traffic loading from AS 5100.2:2017.
- (e) A new informative appendix has been added to provide guidance on the installation of precast access and maintenance chamber systems.

Statements in alphabetical superscript footnotes in tables expressed in mandatory terms are deemed to be requirements of this document. Other notes are only for information and guidance.

The terms “normative” and “informative” are used in Standards to define the application of the appendices to which they apply. A “normative” appendix is an integral part of a Standard, whereas an “informative” appendix is only for information and guidance.

Contents

Preface	ii
Introduction	vi
Section 1 Scope and general	1
1.1 Scope.....	1
1.2 Normative references.....	1
1.3 Terms and definitions.....	3
Section 2 Component structure, manufacture and materials	11
2.1 General.....	11
2.2 Exposure classification.....	13
2.2.1 Exposure classification for internal environments.....	13
2.2.2 Exposure classification of the external environment.....	14
2.3 Concrete materials.....	15
2.3.1 Cementitious materials.....	15
2.3.2 Cementitious material for concrete.....	16
2.3.3 Aggregates.....	17
2.3.4 Water.....	17
2.3.5 Admixtures.....	17
2.3.6 Reinforcement.....	17
2.3.7 Synthetic fibres.....	17
2.3.8 Restrictions on chemical content.....	18
2.3.9 Minimum cementitious material content, maximum water / cementitious material ratio, and maximum water absorption value.....	18
2.3.10 Alternative concrete mixes.....	18
2.4 Cover to reinforcement.....	19
2.4.1 General.....	19
2.4.2 Cover to reinforcement for internal environment.....	19
2.4.3 Cover to reinforcement to the external environment.....	20
2.4.4 Cover to reinforcement for mating surfaces of joints between components.....	21
2.4.5 Additional concrete requirements for internal and external environments.....	21
2.5 Manufacturing processes, and concrete production, placement and curing.....	22
2.5.1 Manufacturing processes.....	22
2.5.2 Concrete batching.....	23
2.5.3 Concrete placing.....	23
2.5.4 Curing.....	24
2.6 Concrete quality control testing.....	25
2.6.1 Machine-made concrete testing.....	25
2.6.2 Wet cast concrete and automated SCC cast concrete testing.....	26
2.7 Elastomeric seals.....	27
2.7.1 General.....	27
2.7.2 Mastic sealants.....	27
2.7.3 Other materials.....	27
Section 3 Manufacture, workmanship and finish	28
3.1 General.....	28
3.2 Test loads for proof and ultimate load testing.....	28
3.2.1 General.....	28
3.2.2 Vertical load testing requirements.....	28
3.2.3 Horizontal load testing requirements (shaft components only).....	29
3.3 Dimensions and tolerances.....	30
3.3.1 Internal diameter of shafts.....	30
3.3.2 Access cover clear opening sizes.....	30
3.4 Measurement of the dimensions.....	30
3.4.1 Straightness.....	30
3.4.2 Squareness of ends.....	30

3.4.3	Shaft diameter.....	31
3.4.4	Wall thickness.....	32
3.4.5	Effective length.....	32
3.4.6	Slab thickness.....	33
3.5	Workmanship and finish.....	33
3.5.1	General.....	33
3.5.2	Joints.....	33
3.5.3	Reinforcement.....	33
3.5.4	Cover.....	33
3.5.5	Classification of defects.....	34
3.6	Marking.....	35
3.7	Handling and storage.....	36
3.7.1	General.....	36
3.7.2	Lifting inserts.....	36
3.7.3	Unreinforced access and maintenance chamber components.....	36
Section 4	Step irons and ladders.....	37
4.1	General.....	37
4.2	Materials.....	37
4.3	Performance testing of installed step irons.....	38
4.4	Step-up and step-down limitations.....	38
4.4.1	Step-up.....	38
4.4.2	Step-down.....	38
Section 5	Access covers and frames.....	40
5.1	General.....	40
5.2	Surface finish.....	40
5.3	Design of lifting keyholes.....	40
Section 6	Sampling and testing of access and maintenance chamber components.....	41
6.1	General.....	41
6.1.1	Facilities for sampling and testing.....	41
6.1.2	Testing procedures.....	41
6.1.3	Testing.....	42
6.2	Type testing.....	45
6.2.1	General.....	45
6.2.2	Manufacture.....	45
6.2.3	Test specimens.....	45
6.3	Routine testing.....	45
6.3.1	General.....	45
6.3.2	Sampling.....	45
6.3.3	Testing.....	45
6.4	Test requirements.....	45
6.4.1	Ultimate load.....	45
6.4.2	Proof load.....	45
6.4.3	Cover to reinforcement.....	46
6.4.4	Water absorption.....	46
6.4.5	Hydrostatic testing of shafts and base units.....	46
6.4.6	Hydrostatic testing of joints.....	46
6.4.7	Vacuum testing of shafts and base units.....	46
6.4.8	Vacuum testing of joints.....	47
6.4.9	Hydrostatic testing of the base to pipe joints.....	47
6.4.10	Dimensional accuracy.....	47
6.4.11	Step irons.....	47
Appendix A	(normative) Product conformity.....	48
Appendix B	(informative) Information exchange between manufacturer and purchaser.....	53
Appendix C	(normative) Methods for load testing of access and maintenance chamber components.....	55

Appendix D (normative) Method for cover testing of reinforced precast concrete access and maintenance chamber components	72
Appendix E (normative) Method for water absorption testing.....	74
Appendix F (normative) Method for hydrostatic testing of a shaft section.....	78
Appendix G (normative) Method for hydrostatic testing of a shaft assembly joint.....	81
Appendix H (normative) Method for load testing of step irons and ladders.....	84
Appendix I (informative) Guide to determining exposure classification.....	86
Appendix J (normative) Method for vacuum testing of a shaft section.....	88
Appendix K (normative) Method for vacuum testing of a jointed shaft assembly.....	91
Appendix L (informative) Method for leak testing of a base to pipe joint seal.....	94
Appendix M (informative) Installation	98
Appendix N (normative) Accelerated curing of wet-cast concrete components.....	102
Bibliography.....	105

Introduction

This Standard was prepared by the Standards Australia Committee WS-006, Concrete Pipes, as a performance-based document for precast concrete access and maintenance chambers.

It was prepared to address advances in current practice, the age of the previous publication of AS 4198 and proposals from industry to move towards greater use of product performance testing. This Standard specifies product performance requirements and excludes normative installation procedures. However, this Standard provides an informative procedure for installation. For further guidelines on recommended installation procedures, reference should be made to the relevant published literature of access and maintenance chamber manufacturers, asset owners, asset owner industry associations and, where appropriate, regulatory authorities.

The in-service life of a precast concrete access or maintenance chamber is dependent on the manufacture, application and installation conditions. This Standard intends that for such installations, service life of 100 years could be expected when components are manufactured in accordance with and installed as recommended by this Standard in the environments defined in this Standard. Components subject to other environments should be assessed for suitability using appropriate engineering judgement. The Standard specifies requirements for concrete access cover assemblies and excludes requirements for metal and polymeric access cover assemblies. The use of some blended cement and chemical admixtures in concrete components is addressed by the Standard.

This document specifically addresses sewerage applications but may also be relevant to drainage, stormwater and other conveyance applications.

Australian Standard®

Precast concrete access and maintenance chambers for sewerage applications

Section 1 Scope and general

1.1 Scope

This Standard describes performance requirements for circular precast concrete access and maintenance chambers systems including chamber materials, component manufacture and quality control. It also describes methods of sampling and testing of precast concrete components manufactured in accordance with the Standard.

This Standard applies to precast concrete access and maintenance chamber components manufactured from steel reinforced, synthetic fibre reinforced or unreinforced concrete that are intended for use in buried sewerage systems. Access chambers conforming to the requirements of this Standard are suitable for a maximum depth to invert of 9 m and to a typical connected pipe diameter not larger than DN750. Similarly, maintenance chambers are suitable for a maximum depth of 6 m and a connecting pipe diameter of not more than DN300.

For other circumstances where depths are greater than 9 m, then specific design matters should be addressed between the designer and the manufacturer.

NOTE 1 Information on means for demonstrating conformity to this Standard is given in [Appendix A](#).

NOTE 2 Guidance on the information to be exchanged by purchaser and manufacturer at the time of an access or maintenance chamber product enquiry or order is given in [Appendix B](#).

NOTE 3 Special design considerations, including high water table, buoyancy uplift resistance, chamber depths greater than 9 m and connected pipes that exceed 750 mm in diameter should be addressed by negotiation between the parties.

NOTE 4 Guidance on the installation of precast access and maintenance chamber systems, including excavation, foundation preparation, placing of units, backfilling, compaction and *in situ* testing is provided in an informative [Appendix M](#).

This Standard does not provide for the following:

- (a) Requirements for cast *in situ* concrete components.
- (b) Ladders that are supplied and installed *in situ*.
- (c) Plastics maintenance shafts.

1.2 Normative references

The following documents are referred to in the text in such a way that some or all of their content constitutes the requirements of this document.

NOTE Documents referenced for informative purposes are listed in the Bibliography.

AS 1012.1, *Methods of testing concrete, Method 1: Sampling of fresh concrete*

AS 1012.3.5, *Methods of testing concrete, Method 3.5: Determination of properties related to the consistency of concrete — Slump flow, T500 and J-ring test*

AS 1012.8.1, *Methods of testing concrete, Method 8.1: Method for making and curing concrete — Compression and indirect tensile test specimens*